

SPECIFICATION OF ACOUSTIC LINING FOR GENERATOR ROOMS AND CHILLER PLANT ROOM

PART 1 GENERAL

- 1.1 Provide acoustic lining for Generator Rooms and Chiller Plant Room.
- 1.2 Acoustic lining shall be fire proof to meet the local requirement with 50 mm thickness.

PART 2 OUTLINE SPECIFICATIONS

Acoustic Lining Specification																				
Sheet metal Face	0.8 mm GMS perforated cover with minimum 23% to 30% open (for example, 3/32" holes on 3/16" staggered centers).																			
Internal Insulation	50 mm thick fiberglass/mineral wool insulation (64 kg/cum density)																			
Support Stud	1.5 mm thick GMS Z channel at 600 mm c/c																			
Insulation Protection	1.5 mil plastic film facing or black tissue (fire & smoke ratings to be verified by others).																			
Acoustic Lining Extent	Refers to architectural or mechanical drawing and acoustic lining shall be applied for not less than 50% of the total wall surface and not less than 50% of the total ceiling surface. Wall lining start from 300 mm from finished floor level to soffit.																			
Acoustical Performance	The acoustical performance shall meet or exceed: <table><tr><td>Octave</td><td>125</td><td>250</td><td>500</td><td>1000</td><td>2000</td><td>4000</td></tr><tr><td>Sound Absorption Coefficient ASTM C423</td><td>0.35</td><td>0.60</td><td>0.95</td><td>0.95</td><td>0.80</td><td>0.65</td></tr></table>						Octave	125	250	500	1000	2000	4000	Sound Absorption Coefficient ASTM C423	0.35	0.60	0.95	0.95	0.80	0.65
Octave	125	250	500	1000	2000	4000														
Sound Absorption Coefficient ASTM C423	0.35	0.60	0.95	0.95	0.80	0.65														

PART 3 SUBMITTAL REQUIREMENTS

- 3.1 The following is the minimum required for review prior to approval of manufacturer and the proposed system:
1. Drawing showing size and fixing detail of acoustic wall lining; and acoustic performance laboratory test data.

PART 4 EXECUTION

- 4.1 Bring to the Architect's attention prior to installation any conflicts with other trades in order to avoid inadequate space or other unforeseen conditions. Corrective work necessitated by conflicts after installation shall be at the responsible contractor's expense.
- 4.2 Obtain inspection and approval of any installation to be covered or enclosed.
- 4.3 Correct, at no additional cost, all installations which are deemed defective in workmanship or materials.

END OF SECTION