

Architectural Particular Specification

CONSTRUCTION PROGRESS DOCUMENTATION

SECTION 1.4

Rev	Date	Description
0	14 APR 2022	First Issue

SECTION 1.4

CONSTRUCTION PROGRESS DOCUMENTATION

PART 1 GENERAL

1.01 SUMMARY

- A. Section Includes:
 - 1. Description of the Works
 - 2. Quality Assurance
 - 3. Tender Requirements
 - 4. Programme of the Works
 - 5. Programme Updates
 - 6. Programme Revisions
 - 7. Recovery Plan
 - 8. Definitions
 - 9. Contractual Milestones
- B. Related Sections :
 - 1. Section 1.3 Substitution Procedures
 - 2. Section 1.5 Submittals Procedures

1.02 DESCRIPTION OF WORK

- A. Scheduling and progress reporting under this Contract will be performed using the critical path method (CPM). Requirements for CPM are included to assure adequate planning and execution of the Works and to assist the Architect, Engineer and the Quantity Surveyor in evaluating the progress of the Works economically and chronologically.
- B. At commencement of the Works, the Contractor shall prepare and submit for the Employer's and Architect's information a Contractor's construction Programme for the Works. The Contractor shall liaise and incorporate the programme of all sub-contractors into the Contractor's programme. The programme shall not exceed time limits defined under the Contract Documents and shall be revised at appropriate intervals as required by the conditions of the Works and Project. The programme shall provide for expeditious and practicable execution of the Works.
- C. At commencement of the Works, the Contractor shall prepare and submit a schedule of submittals which shall be coordinated with the Contractor's construction Programme of Works and which allows the Architect reasonable time to review submittals and shop drawings as defined in the Contract Documents. The schedule shall be submitted to the Architect, two weeks after awards, for approval.
- D. The Contractor shall conform to the most recent schedules. The Contractor shall keep all sub-contractors updated on the most recent schedules and ensure that they conform to these updated schedules.

1.03 QUALITY ASSURANCE

- A. The Contractor and its representatives shall have adequate knowledge of, and experience with, CPM and the Project programming techniques to be utilized in the Contract.
- B. The programme of work for this Project shall be computerized. All costs incurred by the Contractor for the use of CPM and the systems to be utilized in this Project are to be borne by the Contractor.

1.04 PROGRAMME OF THE WORKS

- A. The Project shall be managed by the programme of work using CPM, which the Contractor shall use in planning, organizing, directing, coordinating and executing the Works, and which shall be the basis of evaluating progress of the Works. The programme of work shall be the "Target Schedule" against which all future progress will be compared.
- B. The Contractors programme will indicate areas that can be completed and handed over on a Sectional Completion basis ahead of the Practical Completion date.
- C. The Contractor will indicate the latest date for Consent to be issued by the Building Department for the relevant sections of work in order to maintain the programme.

1.05 PROGRAMME UPDATES

- A. For the purpose of administering this Contract, "programme of work update" shall be defined as the process of applying actual and projected progress information to the actual start and finish dates, percentage complete, remaining duration or projected finish date for all activities in progress during the weekly reporting period. Programme of work update includes minor changes in activity descriptions, but does not include revision of any numeric data, such as activity durations, logic or constrained dates.
- B. Once a week, the Contractor shall gather current progress information as of a given date (Data Date) and submit this data to the Architect.
- C. If the current programme of work update indicates that the current critical path(s) of the programme are in jeopardy, the Architect may direct the Contractor to take such corrective action as may be necessary to recover from the delay(s).

1.06 PROGRAMME REVISIONS

- A. If the Contractor wishes to make changes in its method of operating and/or sequencing of the Works, he shall first write to the Architect in writing stating the reasons for the changes, and provide a written description of the proposed programme of work revisions and draft programme for consideration. Upon review and approval of the changes the Contractor shall provide a reproducible copy of the revised programme of work, which shall be jointly signed by the Employer and the Contractor, signifying acceptance by both parties. At a minimum, proposed programme of work revisions shall not delay contractual milestone dates, modify the overall flow of the Works, or result in an increase in the Contract Sum.
- B. From time-to-time, the Architect and the Contractor may identify minor revisions to the approved programme of work which better represent the intent of the construction plan. Such minor revisions will be incorporated into the approved programme of work upon

agreement by the Employer and the Contractor and will be documented in writing by the Employer.

1.07 RECOVERY PLAN

- A. Should the updated programme of work show the Contractor to be one week, or more, behind programme of work on critical path activities, the Contractor shall immediately devise a plan for recovery of the lost time within the subsequent reporting period. The Contractor's recovery plan will be reviewed at the job site progress meeting, or as soon as possible thereafter. Once approved by the Architect, the Contractor shall immediately put the recovery plan into action.
- B. During the period covered by the recovery plan, the Contractor's progress will continue to be monitored against the approved programme of work. If, by the next Progress Meeting, the Contractor has not recovered from the delay, he shall immediately prepare a revised recovery plan for approval by the Architect.

Persistent failure on the part of the Contractor to recover from its delays will constitute grounds for the Architect to take corrective action, as provided for in the Contract, to ensure satisfactory completion of the Project.

- C. The Contractor shall bear all costs related to recovery from its delays, including costs incurred by the Employer. Refer to liquidated damage provisions as stated in the Special Conditions of the Contract, and Bill of Quantities documents.

1.08 DEFINITIONS

The following terms (and their definitions) shall be used in all Programme of the Works:

- A. Substantial Completion: Substantial Completion of the Project shall mean that all elements of the Project Works are in place and functioning as intended by the Contract Documents, with nothing but minor snagging/rectification list works. All cleaning shall be completed to the satisfaction of the Architect.
- B. Final Completion: Final Completion of the Project is the point at which the Contractor has completed all requirements of the Contract, including correction of snagging / rectification list work, maintenance manuals, and Project close-out activities.
- C. Float: Float related to an activity, or path of activities, is the number of working days difference between the Early Finish date and the Late Finish date. Activities with float values greater than zero (0) may be delayed, without affecting the associated Contractual Milestone, to the extent of the float being reduced to zero. Activities with float values of zero or less are critical to the timely occurrence of the associated Contractual Milestone. Float is not for the exclusive use of either party to the Contract. Float will be administered by the Employer to the benefit of the Project as a whole.

1.09 CONTRACTUAL MILESTONES

- A. The Milestone Date, Possession, as shown in the Programme of Work shall not be extended for any reason except by consent of the Employer.

PART 2 PRODUCTS

NOT USED.

PART 3 EXECUTION

NOT USED.

END OF SECTION