

Architectural Particular Specification

SUBMITTALS PROCEDURES

SECTION 1.5

Rev	Date	Description
0	14 APR 2022	First Issue

SECTION 1.5

SUBMITTALS PROCEDURES

PART 1 GENERAL

1.01 SUMMARY

- A. Section includes the administrative and procedural requirements for submittals including but not limited to the following:
 - 1. Definitions.
 - 2. General submittal procedures.
 - 3. Product data.
 - 4. Shop drawings
 - 5. Samples.
 - 6. Engineering Calculations.
 - 7. Letters of Certification and Testing Reports.
 - 8. Project Closeout Submittals.
 - 9. Submittal Requirement Matrix Tables.
- B. Related Sections:
 - 1. Specification - Preliminaries
 - 2. Particular Specification

1.02 GENERAL SUBMITTAL PROCEDURES

- A. General:
 - 1. The Contractor shall coordinate submittals with requirements listed in the General and Special Conditions of the Contract and Specification.
 - 2. The Contractor shall review and approve prior to submission to the Architect all shop drawings, product data, samples and similar submittals required by the Contract Documents with reasonable promptness and in such sequence as to cause no delay in the Works or in the activities of the Employer, or of separate contractors (if any). The Contractor shall stamp all submittals to the Architect with the Contractor's own submittal review chop. The endorsement with the chop shall mean that all forwarded submittals to the Architect have been reviewed and approved by the Contractor prior to sending. Submittals made by the Contractor which are not required by the Contract Documents, or which have not been reviewed and approved by the Contractor, shall be returned without action.
 - 3. The Contractor shall perform no portion of the Works requiring submittal and review of shop drawings, product data, samples or similar submittals until the respective submittal has been approved by the Architect.
 - 4. By the approval and submission of shop drawings, product data, samples and similar submittals, the Contractor acknowledges that he has determined and verified materials, field measurement, clearances, and field construction criteria related thereto, and has checked and coordinated the information contain within such submittals with the requirements of the Works and of the Contract Documents.

- B. Distribution:
1. Send submittals direct to the Architect and relevant consultants as required by relevant Specification sections.
 2. Submit one copy of the approved shop drawings to the Employer.
- C. General Format:
1. Transmit each submittal with the Submittal Transmittal Form (STF).
 2. Sequentially number the STF. Resubmittals to have original number with an alphabetic suffix.
 3. Identify Project, Contractor, subcontractor or supplier; pertinent Drawing sheet and detail number(s), and Specification section number on the STF.
 4. Submit all submittals required by section together in a single submittal.
 5. Coordinate submission of related items within each section together in a single submittal.
 6. After submittal and review process are completed, provide copies for inclusion within Record Documents set.
- D. Each shop drawings shall have a blank area eight (8) cm high by ten (10) cm wide, located adjacent to the title block. The drawing title block shall display the following :
1. Number and title of the drawing.
 2. Date of drawing or revision.
 3. Name of Contractor and subcontractor, if applicable, submitting drawing.
 4. Clear identification of contents and location of the work.
 5. Specification section and paragraph number.
- E. If shop drawings show variations from the Contract requirements because of standard shop practice or for other reasons, the Contractor shall describe such variations in its letter of transmittal to the Architect. If acceptable, the Architect may approve any or shall such variations. If the Contractor fails to describe such variations, he shall not be relieved of the responsibility for executing the Works in accordance with the Contract, even though work shown on such drawings has been permitted to proceed for fabrication/manufacture or construction.
- F. Substitution submittal requirements shall be as indicated in Section 1.3 – Substitution Procedures.

1.03 SUBMITTALS

- A. Product Data:
1. Submit legible copies indicating the products submitted as those specified.
 2. Submit the type of data specified in individual Specification sections.
 3. Data to consist of the exact manufacturer, model and type specified and noted by circling or highlighting. The graphical method of identification is to be reproducible by photocopying.
 4. Submit as noted at the end of this section.

B. Letters of Certification and Testing Reports:

1. Provide Letters of Certification signed by the Contractor, indicating that installer/applicator performing the work is approved by the Manufacturer.
2. Refer to each section for specific requirements.
3. Manufacturer's product and technical performance data, e.g. fire-rating resistance, etc and Manufacturer's material safety data sheet with Manufacturer's written certification.
4. Testing Reports conducted on a specified product that substantiates its technical performance, fire-rating, physical properties, suitability and applicability, and compliance with relevant construction and material standards.

C. Shop Drawings:

1. Shop drawings shall be submitted to the Architect or Consultants as indicated using the Submittal Transmittal Form (STF) attached.
2. Submit STF as specified by section indicated herein.
3. Submit in the form of sepia or reproducible transparency.
4. Each submittal to the Architect or Consultant Engineers shall consist of one (1) reproducible copy and two (2) prints of shop drawings and layout drawings, submittals to other consultant's submittals shall consist of one (1) reproducible copy.
5. All electronic copy shall be in AutoCAD 2009.

D. Engineering Calculations :

1. Engineering Calculations prepared by a Hong Kong Registered Structural Engineer signed and stamped. 1 copy each to the Consulting Structural Engineer, the Architect, the Contractor, and the local Building Authorities if so required.

E. Samples:

1. Submit 3 samples for each type of product and material. After review the following distribution will be followed. One sample shall be retained by the Architect for his record. One sample shall be retained at the project site for the Contractor's record. One sample shall be returned to the sub-contractor, or supplier, upon review by the Architect. Samples submitted not adhering to this requirement will be returned and not reviewed.
2. All samples shall be clearly labeled stating the submittal number, product name, model number, colour and finish types, Specification section number and location(s) on the project.
3. Samples shall be a minimum of 300mm x 300mm, unless noted otherwise in specific sections of the Specification. They shall be packaged in protective parcel packing to prevent damage during delivery.
4. All sample items, packaging, custom tariffs, and delivery costs for required sample submittals shall be at the expense of the Contractor.

1.04 PROCEDURES

A. General

1. All Submittals are to include a completed STF. The Specification Section number and Title must be indicated on the Form.
2. The Contractor shall instigate and maintain a submittal log for the Project. The log is to identify the submittal number, drawing number and title, date submitted,

date returned, action and the total of the days under review, since the submission date. The Contractor shall issue weekly updated log to the Architect for review.

B. Procedures for Submittals:

1. Submit each Section's data complete by Section. Partial Sections will be returned and marked "Revise and Resubmit".
2. Submit only those items specified, substitutions will not be allowed.
3. Apply Contractor's stamp, signed or initialed certifying that review, verification of products required, field dimensions, adjacent construction Work, and coordination of information, is in accordance with the requirements of the Works and Contract Documents. Submittals will be returned "unreviewed" if this procedure is not adhered to.
4. Revise and resubmit submittals as required, identify all changes made since previous submittal by bubbling altered area(s). Submissions will be returned "unreviewed" if this procedure is not followed.
5. Distribute copies of reviewed submittals to sub-contractor and other concerned parties. Instruct parties to promptly report inability to comply with provisions.
6. Identify variations in product or system limitations which may be detrimental to successful performance of the completed Works.
7. Distribute one copy of reviewed shop drawings to the Project Manager, Architect, Site Architect, and other Consultants.

C. Action Taken

1. Product Data:
 - a. Data and Calculations along with the STF will be received and reviewed by the Architect or Consultant for verification of conformance. The submission will be marked "For Information" if criteria for conformance is met.
2. Letter of Certification and Test Report:
 - a. Received by the Review Architect or Consultant along with the STF. The submission will be marked "For Information" if criteria for Certification is met.
3. Shop Drawings:
 - a. The submittals will be received by the Architect / Consultant and will be reviewed and one reproducible copy of each shop drawing returned to the Contractor with one of the following actions indicated.
 1. "A" - Final check before proceeding with work concerned.
 2. "B" - Attention to matters set out in notes hereon/ letter dated ...
 3. "C" - Submission of revised drawing required.
 4. "D" - Rejected.
 5. "I" - For Information.
 6. "U" - Unreviewed.

- D. Copies of drawings returned to Contractor marked with either notation "A" or "B" are authorized to proceed with the fabrication/ manufacture or construction covered by such returned copies, provided that such fabrication/manufacture or construction shall be subject to the comments, if any, shown on such returned copies. Although fabrication/ manufacture or construction may proceed on a notation "B" review (with comments), the Contractor shall incorporate the comments, resubmit, and obtain notation "A" within fourteen (14) calendar days thereafter.

Permission to proceed shall not constitute acceptance or approval of design details, calculations, analyses, test methods or materials developed or selected by the Contractor and shall not relieve the Contractor from full compliance with the Contract requirements.

- E. Copies of drawings returned to the Contractor marked with notation "C" shall be corrected as necessary and required, and such drawings shall be resubmitted in the same manner as before. No fabrication or erection shall occur until approved notation "B" or "A" is received.
- F. Copies of drawings returned to the Contractor marked with notation "D" are rejected. Alternative materials submittal is required to be made.
- G. For Information: The drawing/ data has been reviewed by the Architect/ Consultant as additional information to the actioned shop drawings.
- H. Unreviewed: The submission does not either comply with the required procedures and/or is not a required submittal.
- I. Copies of drawings returned to the Contractor marked with either notation "B", "C" "D" or "U" shall be resubmitted to the Architect no later than fourteen (14) calendar days after date of receipt by the Contractor of such copies of drawings and in no case later than twenty-one (21) calendar days after the date of the Architect's transmittal letter.
- J. Review of the Contractor's drawings by the Architect shall not be held to relieve the Contractor of any of these obligations to meet all the requirements of the Contract or relieve the Contractor of the responsibility for the correctness of such drawings. The Contractor shall, at its expense, make any changes in the design which are necessary to make the work conform to the provisions and intent of the Contract.
- K. Resubmittals of drawings will be handled in the same manner as first submittals. On resubmittals the Contractor shall direct specific attention, in writing or on resubmitted drawings, to revisions other than the comments made by the Architect on previous submissions. The Contractor shall make any corrections required by the Architect.
- L. When the drawings have been satisfactorily completed, the Contractor shall carry out the fabrication/manufacture or construction in accordance therewith and shall make no further changes therein except upon written instructions from the Architect.
- M. In the event that a change occurs to a previously reviewed drawing and the Contractor has received from the Architect authorization to proceed with the change, the Contractor shall revise the previously reviewed drawing to reflect the latest reviewed change and resubmit the drawing to the Architect.
- N. The Contractor shall be responsible for, and bear all costs of damages which may result from the ordering of any material or from proceeding with any part of the Works prior to receiving permission to proceed from the Architect.
- O. The Contractor shall bear the responsibility of any costs associated with delay of overall job schedule due to failure of timely, or orderly submission.
- P. Coordination:
 - 1. Time
 - a. A review period of three (3) weeks, and in no less than ten (10) working days, shall be observed from the time the submissions are received in the Consultants offices until the time the submissions are returned from the Consultants office.
 - b. The Contractor shall promptly submit submittals so as not to impede the progress of the Works and to provide the Architect with the designated time for review.

- c. Coordinate work with the Project programme of the Works with due consideration of procurement periods for materials and equipment. The Contractor shall produce a programme for the production of shop drawings and submit to the Architect for review and approval. The programme shall be comprehensive and shall include the timing for submission and the projected content of each submittal. The Contractor shall make allowance within the programme for the resubmission of information as well as for the designated time for review. The review period of three (3) weeks, and in no less than ten (10) working days, is based on the assumption that the Contractor will make phased submissions of shop drawings, for each package. Should the complete set of shop drawings for a package be submitted in its entirety at one time, the total review period will be extended to thirty (30) working days.

2. Project Record Documents

- a. Record Documents shall be kept current with appropriate fields updated as necessary.

Q. Record Document Procedures :

1. The Contractor shall maintain an accurate record of all changes to the Works and record these changes on the Contract Documents for the duration of the Contract. The Record Documents shall provide accurate factual information regarding all aspects of the Works, both concealed and visible, to enable future modification of the Works to proceed without lengthy and extensive site measurement, investigation and examination.
2. The Contractor shall delegate responsibility for maintenance of Record Documents to one person. Submit details of this person to the Architect for approval.
3. The Contractor shall thoroughly coordinate changes within Record Documents, making entries on each page of the Specification and each sheet of the Drawings and other Documents where such entry is required to show change.
4. Records shall be accurate so that future searches for items shown in Contract Documents may rely reasonably on information obtained from the Record Documents.
5. The Contractor shall make entries within 24 hours after receipt of information that a change has occurred.

6. Record Drawings and Shop Drawings :

- a. Use an erasable red coloured pencil (not ink or indelible pencil), clearly describe change by graphic line and notation.
- b. Date all entries next to each entry.
- c. Draw a “cloud” around entry and the area or areas affected.
- d. In event of overlapping changes, the Contractor shall use different contrasting colours for overlapping change.
- e. The Contractor shall mark each item to record actual construction including :
 - 1) Measured depths of foundations in relation on finish floor datum.
 - 2) Measured horizontal and vertical locations of underground utility lines and appurtenances, referenced to permanent surface improvements.
 - 3) Measured locations of building interior utilities and appurtenances concealed in construction, referenced to visible and accessible features of the Works.
 - 4) Field changes of dimensions and construction details.
 - 5) Details not on original Contract Drawings.
- f. All entry text shall be in English.
- g. The Contractor shall indicate as-built location of post-tensioning cables and other buried structural elements onto the Record Drawings.

In addition, the Contractor shall permanently mark the position of all post-tensioning cables on the Works, as the project proceeds.
- h. The Contractor shall indicate buried utility and services runs and layouts onto the Record Documents.

7. Specifications :

- a. The Contractor shall mark and record at each Section the description of actual products installed, including the following :
 1. Manufacturer's name and product model number.
 2. Alternate products or manufacturers utilized.
 3. Changes made by addenda or modifications to the Contract requirements.
- b. All entry text shall be in English.

R. Maintenance of Record Documents :

1. On all items forming part of the record documents the Contractor shall mark “RECORD DOCUMENTS-JOB SET” prominently on cover and other appropriate locations.
2. The Contractor shall maintain Record Documents – Job Set completely protected from deterioration and from loss and damage until completion of the Works and transfer of all recorded data to final certified project record documents. Records/as built drawings shall be compiled as the works progress.
3. The Contractor shall provide a suitable method for protecting the Record Document - Job Set taking into consideration the Contract completion time, probable number of occasions that Record Documents - Job Set will be taken out for new entries and for examination, and the conditions under which these activities will be performed. Do not use Record Documents - Job Set for any purpose except entry of new data and for review by Architect, until start of transfer to final project Record Documents.

S. Final Certified Record Documents :

1. The Contractor shall submit to Architect completed Record Documents as part of Contract closeout submittals.
2. The Contractor shall stamp, sign, and date each page of final Record Specifications, Record Drawings, and Record Submittals, Certifications, and Test Reports certifying accuracy of the information contained thereon.
3. The Contractor shall furnish the Employer with a minimum of 2 sets of the Record Documents.

1.05 OPERATION AND MAINTENANCE MANUALS

A. Format :

1. The Contractor shall prepare data in the form of an instruction manual, using the following format:
2. Binders: Commercial quality, A4 three-ring binders with hardback, cleanable, plastic covers.
3. Cover : Identify binder with typed or printed title "Operation and Maintenance Instructions;" list title of Project and identify subject matter of contents.
4. Contents shall be arranged by systems under Specification Section numbers.
5. Provide tabbed fly leaf for each separate product and system, with typed description of product and major component parts or equipment.
6. Text : Manufacturer's printed data, or typewritten data on 20-pound white paper, printed on both sides.
7. Drawings : Provide with reinforced punched tab. Bind in with text; fold larger drawings to size of text pages.

B. Contents, Each Volume :

1. Table of Contents : Provide title of Project; names, addresses and telephone numbers of Architect, Review Consultant (e.g. Specialist Consultants for BMU, Curtain Wall, Lifts etc.) and the Contractor.
2. For Each Product or System: List names, addresses, email (where available), telephone and fax numbers of subcontractors and suppliers, including local sources of supplies and replacement parts.
3. Product Data: Mark each sheet to clearly identify specific products and component parts and data applicable to installation and delete inapplicable information.
4. Drawings: Provide supplement product data to illustrate relations of component parts of equipment and systems, and provide control and flow diagrams. Copies of project Record Documents SHALL NOT be used as maintenance drawings.
5. Type Text: As required to supplement product data. Provide logical sequence of instructions for each procedure, incorporating manufacturer's instructions. Text shall be in English & Chinese.

1.06 SNAGGING

- A. As each portion of the Works is identified by the relevant sub-contractor as being complete, the Contractor shall inspect the Works for compliance with the Contract Documents. Once the Contractor has endorsed that the Works comply with the Contract Documents, the Works shall be presented to the Architect for review.
- B. The Architect will review the Works and identify items of the Works that are not in compliance with the Contract Documents.
- C. The Contractor shall make due and proper allowance within the Programme of Works for the snagging work and any required rectification of the defects.
- D. The Contractor shall maintain on a computer data base all snagging/ rectification items identified by the Architect, Consultants and Contractor as being in non-conformance with the Contract Documents of the Works. The Contractor shall inspect and confirm that any non-conforming items are rectified prior to presenting the items to Architect for acceptance. Only after the Architect has accepted the item as being in conformance with the Contract Documents is the item to be removed from the data base.
- E. The Contractor shall programme the snagging work so that the completed work is presented to the Architect prior to the works being covered up by subsequent trades.

1.07 CONTRACT CLOSEOUT

- A. Documentation of scheduled Date of Completion: Comply with Procedures in General and Special Conditions of the Contract.
- B. When the Contractor considers the Works to be at practical completion, he shall submit the Completion Certificate to the Architect certifying that :
 - 1. Contract Documents have been reviewed.
 - 2. The Works have been inspected.
 - 3. The Works are completed and in accordance with Contract Documents.
 - 4. The Works are ready for inspection by the Architect.
- C. Final Closeout Submittals: Comply with procedures in the Preliminaries section of the Contract for construction for the thinning of the submission of the record documents.
 - 1. Warranties and Bonds.
 - 2. As-Built Record Documents.
 - 3. Operations and Maintenance Manuals with spare parts lists.
 - 4. Close-out Documents Books in A4 binders.
 - a. Copy of the original of Occupation Permit issue by the Building Authority.
 - b. Submittals required by governing authorities.
 - c. Final Application for Payment listing original Contract Sum, previous adjustment, previous payments and sum remaining due.
 - d. Final list of Subcontractors used.
 - e. All Manufacturer's Review Forms filled out and signed.
 - f. Practical Completion defects list showing items completed and approved by the Architect.

PART 2 PRODUCTS

(NOT USED)

PART 3 EXECUTION

3.01 REQUIRED SUBMITTALS BY SECTION

- A. Refer to other submittal requirements in Consultant Engineers' Contract Documents.

The General and Special Conditions of the Contract, Drawings, Specification and Schedule of Rate.

- B. Submittals under this specification section that are generally required to be sent to the Architect or Consultant, indicated in the submittal requirement matrix tables at the end of this section. The requirements identified in the matrix are for information only refer to each specification section for specific requirements.

END OF SECTION