

## Architectural Particular Specification

# SITE CLEANLINESS

## SECTION 1.9

| Rev | Date        | Description |
|-----|-------------|-------------|
| 0   | 14 APR 2022 | First Issue |
|     |             |             |
|     |             |             |
|     |             |             |

## **SECTION 1.9**

### **SITE CLEANLINESS**

#### **PART 1 GENERAL**

##### **1.01 SCOPE OF WORK**

- A. The Contractor shall perform Daily Cleaning and Weekly Tidying of the Site including Public Cleaning Areas. The extent of the Public Cleaning Areas required for cleaning are deemed to be within 5 meters on the periphery outside the barriers or hoardings, or determined by the Architect's Representative on site for each work location based on the requirements in the Particular Specification, and taking into account the actual site condition before work commences.
- B. The Contractor shall draw up in the Waste Management Plan where appropriate, a system on waste management, and maintenance of cleanliness and tidiness of the Site including, but is not limited to, the methods and provisions including the proposed areas for on-site sorting, separation, storage and disposal of waste materials, and the proposal of how to maintain the Site in clean and tidy condition. The Contractor shall provide the necessary facilities, receptacles and transport for the temporary storage, disposal and removal of different types of wastes.
- C. The contractor shall clean and tidy up the entire site before handover to client.
- D. The contractor shall be responsible for the completion of cleaning works up to the satisfaction of Architect and clients and all such time and cost shall be deemed to be included in the contract.
- E. Notwithstanding the requirement in this section, it is the contractor's responsibility to ensure that all cleaning methods, tools and cleaning agents used shall not cause any damage to the materials. Any damages due to cleaning shall be rectified by the contractor and no claims to time and cost will be entertained in this regard.

##### **1.02 DAILY CLEANING**

- A. "Daily Cleaning" shall include cleaning and tidying up after work of tools, equipment, unused materials, storage areas and common areas such as passageways, daily removal of waste materials from works areas, removal of any rubbish and debris dumped into the Site by the public and, without derogating from the generality of the foregoing, shall include, but is not limited to, all the items subject to checking as listed in sub-clause (c)(ii).
- B. The Contractor shall develop inspection checklist for Daily Cleaning for the approval of the Architect's Representative. The inspection checklist shall be reviewed and updated whenever there is a change in work nature or work location and re-submitted for approval by the Architect's Representative. The inspection checklist shall include an assessment on the cleanliness and tidiness of all work locations, plus the Public Cleaning Areas. Items to be checked against for each work location shall include, but are not limited to, the following:
  - 1. Maintenance of passageways, common accesses and public areas free of obstruction;
  - 2. Proper storage and stacking of materials;
  - 3. Proper placement and storage of tools and equipment after work;
  - 4. Proper sorting, storage and/or disposal of waste materials in accordance with the Waste Management Plan;

5. Proper securing of hoarding, barriers, guarding, lighting, and signage of works;
  6. Prevention and removal of water ponds and flooding;
  7. Clearing of stockpiling and wastes arising from the Works;
  8. Conditions of cleanliness and tidiness of the Site including Public Cleaning Areas in the perspective of the general public; and
  9. Other cleaning requirements as instructed by the Architect's Representative.
- C. The Contractor shall assign person(s) to inspect the Site after each Cleaning Day's work. The assigned person shall check and ensure the cleanliness and tidiness of the Site, complete the inspection checklist, record the areas requiring improvements, and take photographs of areas where cleaning and tidying up works have been done and where improvement actions are required.
- D. The Contractor shall notify the Architect's Representative the time schedule for Daily Cleaning on every Cleaning Day and the name of the assigned person as referred to in sub-clause (c)(iii) above responsible for the inspection and checking after each Cleaning Day.
- E. The Contractor shall submit, in the morning of the day (which is not a General Holiday) following a Cleaning Day, the inspection checklist, records and photographs prepared pursuant to sub-clause (c)(iii) above to the Architect's Representative for checking and recording.
- F. The Architect's Representative may carry out inspections and surprise checks to verify the Contractor's performance on cleanliness and tidiness of the Site before the noon of the day (which is not a General Holiday) following a Cleaning Day. The Contractor shall not be entitled to any payment for the item for "Daily Cleaning" for a Cleaning Day if the performance of the Contractor on cleanliness and tidiness for any part of the Site on that Cleaning Day is not carried out to the satisfaction of the Architect's Representative. The Architect's Representative shall notify the Contractor and record in the Site Diary for any non-payment of the item for "Daily Cleaning" on a Cleaning Day and the areas of dissatisfaction for improvement by the Contractor.
- G. The Contractor shall in the morning of every Cleaning Day before work commences inspect and remove any rubbish and debris that may be littered by the public over the night within any area which cleanliness and tidiness the Contractor is required to maintain under this Contract before the inspection by the Architect's Representative.

### **1.03 WEEKLY TIDYING**

- A. "Weekly Tidying" shall include the cleansing and tidying up of the common areas and accesses, cleansing and/or re-conditioning of hoardings, barriers, guarding, lighting, signage and/or traffic cones, cleansing of external covers for plant and equipment, removal of waste and debris etc. so as to ensure that the plant and equipment, hoardings, as well as the Site as a whole, to be clean and tidy in the perspective of the general public and, without derogating from the generality of the foregoing, shall include, but is not limited to, all the items subject to checking as listed in sub-clause (d)(ii).
- B. The Contractor shall develop inspection checklist for Weekly Tidying for the approval of the Architect's Representative. The inspection checklist shall be reviewed and updated whenever there is a change in work nature or work location and re-submitted for approval by the Architect's Representative. The inspection checklist shall include an assessment on the cleanliness and tidiness of the Site conditions at various work locations, plus including the Public Cleaning Areas. Items to be checked against for each work location shall include, but are not limited to, the following:-
1. Thorough cleansing of passageways, common accesses and public areas;
  2. Re-organizing of storage materials for better utilization of storage spaces and safe stacking if appropriate;

3. Maintenance and re-conditioning of tools and equipment;
  4. Cleansing of external covers for plant and equipment;
  5. Collection and removal of disposed waste materials off site in accordance with the Waste Management Plan;
  6. Cleansing, re-conditioning and/or replacement of hoarding, barriers, guarding, lighting, and signage of works to good working condition;
  7. Clearing of drains and channels to prevent flooding; and
  8. Other cleansing requirements as instructed by the Architect's Representative from the perspective of the general public.
- C. The Contractor shall assign person(s) to inspect the Site after each Cleaning Week Day's work. The assigned person shall check and ensure the overall cleanliness and tidiness of the Site, complete the inspection checklist, record the areas requiring improvements, and take photographs of areas where overall site cleaning and tidying up actions have been done and where improvement actions are required.
- D. The Contractor shall notify the Architect's Representative the time schedule for Weekly Tidying on every Cleaning Week Day, and the name of the assigned person as referred to in sub-clause (d)(iii) above responsible for the inspection and checking after each Cleaning Week Day.
- E. The Contractor shall submit, in the morning of the day (which is not a General Holiday) following the Cleaning Week Day, the inspection checklist, records and photographs prepared pursuant to sub-clause (d)(iii) above to the Architect's Representative for checking and recording.
- F. The Architect's Representative shall, together with the Site Agent, check and inspect the overall cleanliness and tidiness of the Site on the day (which is not a General Holiday) following the Cleaning Week Day. The Architect's Representative shall advise the Contractor whether his performance is to his/her satisfaction, or if not, where improvement actions are required.
- G. The Contractor shall promptly rectify the defects identified by the assigned person as referred to in sub-clause (d)(iii) above, and/or the Architect's Representative. The Contractor shall not be entitled to any payment for the item for "Weekly Tidying" for a Cleaning Week Day if the Contractor fails to rectify the identified defects pursuant to sub-clauses (d)(iii) and (d)(vi) above to the satisfaction of the Architect's Representative before the end of the day (which is not a General Holiday) following the Cleaning Week Day.
- H. The Contractor shall in the morning of every Cleaning Week Day before work commences inspect and remove any rubbish and debris that may be littered by the public over the night within any area which cleanliness and tidiness the Contractor is required to maintain under this Contract before the inspection by the Architect's Representative.

#### **1.04 METHOD STATEMENT FOR CLEANING DIFFERENT FINISHES**

##### **A. Aluminium Cladding**

Cement drops, stain and dust to be removed by shaver blades and fine metal brush, rinsed with water and dried by towels. Coating finish must not be scratched-off or affected in all cases.

##### **B. Granite and Marble Works**

Cement drop, stain, marks to be removed by shaving blades or fine metal brush, dust to be rinsed by water and light detergent. Machine polishing to a surface upon cleansing work if required.

C. Glazing

Use shaver blades and scrub sponge.

D. Tiles

Cement drops and stains to be removed by fine metal brush and shaver blades, then use detergent to clean the surfaces.

E. Sanitary Fitting

Stains to be removed by shaver blades and scrub sponge and then rinsed with water. Use towel to dry the surface.

F. Woodworks

Clean dust with sweep and then towelled clean.

G. Window Frame

Cement drops, stain and dust to be removed by shaver blades, and fine metal brush, rinsed with water and dried by towels.

H. Granite and Concrete Block Paving, Homogenous Tiles, Artificial/Reconstituted Granite Tiles

Use blade to remove soil dumping and rubbish, then clean surface with high-pressure water jet ( > 200 PSI) to remove cement, sand and other stains

I. Wash Pebble Finish

Use high pressure water jet (>200 Psi) to rinse the wash pebble surface and remove all cement drops and stains. Only minimal detergent will be permitted.

**1.05 PROTECTION**

- A. All glazing to be protected with water-solvent plasticide before applying sulphuric acid for cleaning external wall.
- B. Weaker acid of higher pH value shall be used for cleaning granite/marble/sanitary fitting.
- C. To use high pressure water jet (in lieu of sulphuric acid) for planter and external area as far as practicable.

**END OF SECTION**