

Architectural Particular Specification
ENTRANCE DOOR MAT
SECTION 10.4

Rev	Date	Description
0	14 APR 2022	First Issue

SECTION 10.4

ENTRANCE DOOR MAT

PART 1 GENERAL

1.01 SUMMARY OF WORK

- A. The Work of this Section includes, but is not limited to, the furnishing and installation of entrance floor mats and frames, and the associated drainage works outside of doors of entrance areas as indicated in the Drawings.
- B. The Contractor shall coordinate to:-
 - 1. Contractor shall design and coordinate the fall arrest system(s) such that the respective structural integrity and watertightness of the roofs to which the fall arrest system(s) are installed will not be affected.
 - a. Verify the exact dimensions of the floor recess(es) to accommodate the floor mat.
 - b. Arrange the drainage works for the floor recess to be properly drained.

1.02 REFERENCE

(NOT USED)

1.03 QUALITY ASSURANCE

(NOT USED)

1.04 PERFORMANCE REQUIREMENTS

- A. Works shall conform to all relevant statutory ordinances, regulations, orders, codes of practice in force at the time of signing of the Contract.
- B. The Contractor shall allow for site tolerances, discrepancies and changes in the building layout, where the principles and intent of the signs are not affected.
- C. The mat system shall provide an effective barrier against soil and moisture by retaining wet and dry debris at the point of entry to a building.
 - 1. Withstand continuous and high volume of pedestrian traffic;
 - 2. Provide effective draining;
 - 3. Allow dirt, mud and moisture to collect underneath the system rather than on the surface;
 - 4. Be slip-resistant, safe and quiet;
 - 5. Eliminate metal-to-metal rattle;
 - 6. Be dimensionally stable;
 - 7. Be easily rolled and cleaned.
- D. The mat system shall provide spaces between inserts to allow dirt and moisture to fall through the mat into the matwell below. The system shall be designed such that the dirt and moisture can be removed by lifting the mat and cleaning out the matwell as well as deep cleaning the mat itself.
- E. The mat system shall be designed such that the aluminium profile walls are resistant to deformation and enables new insert to be replaced in the same aluminium profile in the case of damage and difficult stains.

- F. Mats are delivered adjusted to the recessed well size, with the following tolerances:
1. Panel direction: -4mm. /+0mm
 2. Traffic direction: -4mm. /+0mm
- G. The manufacturer of the entrance floor mat must be in possession of a valid quality system certificate showing compliance with ISO9001:2008 quality system.
- H. The manufacturer of the entrance floor mat must be in possession of a valid environmental management system certificate showing their operation is in compliance with ISO14001:2004 system.
- I. The manufacturer of the entrance floor mat must be in possession of a valid occupational health and safety management system certificate, showing their operation is in compliance with OHSAS 18001:2007 system.

1.05 ENVIRONMENTAL REQUIREMENTS

(NOT USED)

1.06 ENVIRONMENTAL, CLIMATIC & PSYCHOMETRIC CONDITIONS

(NOT USED)

1.07 SUBMITTALS

- A. Shop Drawings indicating the following particulars shall be submitted to the Architect for review without objection:-
1. Indicate profiles, sizes, connection attachments, reinforcing, anchorage size and type of fasteners and accessories.
 2. Indicate the interface detail with drainage below.
 3. Include erection drawings with plans and details where applicable. Layout and plan drawings shall be drawn at 1:50 scale. Detail drawings at 1:1 scale.
 4. Indicate location, and size of all cut floor mats.
 5. Methods to be used to control employee exposure to falls while they are in the "Danger Zone".
- B. Samples
- Submit samples with range of colors of each component, including aluminium profile, insert modules, aluminium angle bar, rubber cushions and aluminium T-bars if required, for architect's approval prior to the construction of any full size prototypes.

1.08 PRE-INSTALLATION CONFERENCE

(NOT USED)

1.09 DELIVERY STORAGE AND HANDLING

- A. The floor mats shall be stacked horizontally on European standard pallets. When delivered to site, the floor mat system shall be wrapped around a cardboard tube and in a plastic foil with protective wooden discs at both ends. The floor mat is to be rolled out inside the prepared recess after the installation of angle bar if required.
- B. The floor mat and floor grid system shall be installed in strict accordance with the manufacturer's guidelines and installation manual.

1.10 MOCK-UPS

This part shall be read in conjunction with Clause 8.03 of Specification Preliminaries for the requirements for prototypes and trial areas.

1.11 TESTING

(NOT USED)

1.12 WARRANTY

This part shall be read in conjunction with Clause 8.04 of Specification Preliminaries for the list of material/ system requiring joint written guarantees.

1.13 SPARE PARTS

This part shall be read in conjunction with Clause 8.05 of Specification Preliminaries for the list of spares and spare parts.

PRODUCT

1.14 APPROVED MANUFACTURER

(NOT USED)

1.15 MATERIALS / SYSTEMS

A. The mat system shall comprise the following components:-

1. Aluminium profile shall have a crush resistance of 119kg/cm³ for 22mm profile and the maximum height of profile including insert is 25mm. It shall comply with the following standards: PN EN 573-3, EN AW-6063, PN EN 755-9, DIN AlMgSiO 5 F22, and PN PA 38.
2. Types of insert (brush, rubber, ryps or exclusive) with drying and cleaning action to be selected and approved by Architect. Rubber inserts shall comply with the following standards: PN 66C – 9416 Class 7, mix on base EPDM according to BN-80/6613-04; Hardness 70° Sha.
3. Aluminium angle bar of 20x20x2mm
4. Rubber cushions (if necessary)
5. Aluminium T-bars of 20x20x2mm – Mat of big size shall be divided into lighter modules which are easier to roll out and take out of the recess during period cleaning.
6. Proprietary recessed matwell frame should be used.

1.16 ANCILLARY MATERIALS

(NOT USED)

1.17 FABRICATION

(NOT USED)

1.18 WORKMANSHIP

(NOT USED)

PART 2 EXECUTION

2.01 EXAMINATION / INSPECTION

(NOT USED)

2.02 PREPARATION

- A. Before installation, any irregular sub-floor condition such as dampness, leaks and indentation that would affect quality of the finished floorings, shall be removed or patched.
- B. All cracks, holes and imperfections of the sub-floor shall be patched.

2.03 INSTALLATION / APPLICATION

- A. Entrance mat delivered to job sites shall be in rolls. In prepared recess (after installation of angle bar when required), it can be simply rolled out inside the recess.
- B. The system shall be installed in accordance with manufacturer's guidelines and installation manual.
- C. A recessed mat shall be installed into a matwell that has been set into an existing floor finish and fits flush with the surrounding floorcoverings. Matwell frames are used to protect and strengthen the matwell, protect the exposed edge of the floorcovering and provide safe transition to the surrounding area. The base of the matwell is screeded to suit the required height of the mat and to provide a flat, sound surface.
- D. Draining system shall be supplied & installed by contractor if necessary for leading off water and dirt.
- E. All flooring components should be supplied by the Manufacturer. Accessories, when supplied by sources other than the Manufacturer, should be approved by the manufacturer to ensure compatibility and integration.
- F. General contractor or owner shall provide secure storage and holding area.
- G. Measurement of Mat / Installation:
 - 1. Depending on the phase of project, it is possible to
 - a. Fit a recess dimensions to an ordered mat- a mat is made firstly, secondly a recess. It is recommended especially for non-rectangle mat.
 - b. Fit dimensions of a mat to an existing recess on floor for a mat.
 - 2. Installation in recess
 - a. Ready-to-use (outside dimensions)

Working space for normal exploitation shall be included. Working space is 2mm on each side of the mat, it means 4mm for length and 4mm for width of the mat.
 - b. Recess (inner dimensions)

If angle bar is included around the mat, width of angle bar shall be deducted from the inner dimensions of the recess

2.04 TOLERANCES (NOT USED)

PART 3 Cleaning

- A. For top performance, the mat should be vacuumed daily.
- B. To retain freshness, the mat needs monthly extraction cleaning and rapid drying.

3.02 PROTECTION (NOT USED)

END OF SECTION